
Step 1:

- Connect via Wi-Fi as normal using AP
- Once connected to the unit, entering Monitoring





Step 2:

- Turn unit off and back on again
- Press Delay End unit you reach 17h, then hold High Temp Wash until
 AS appears, press Start and close door
- Smart install mode has started and the number 1 will appear
- Once Smart Install has started, you will return to the Monitoring Page
- Periodically switch to another Monitoring Page in order to keep the connection active





Step 3:

- Step 3 is where the Disconnection happens
- If it makes it to Step 4, the Smart Install will complete



■ Monitoring				
Recent cycle	Temp. & sensor	Motor	Pump & va	live ETC
		Check	OK	
Name	Va	lue	Ur	nit Reference
Actual power	0.0)		
Dry fan	OF	F	State	on, off
Alternation	OF	F	State	on, off
Alternation switch stat	cus 0.0)		0, 1
Motor check code	0.0)		1~6
Detergent Dispenser	OF	F	State	on, off
Dry fan motor RPM	0.0)	RPM	3000 rpm or more
Pump motor target RP	M 0.0)	RPM	Depends on performance specifications, 2200~3400rpm
Pump motor actual RF	PM 0.0		RPM	Should come out similar to target rpm

Step 4:

- Once Smart Install completes, OT will appear
- Close the door and complete overall checkup
- It will pass immediately and you can upload the pass result
 ***On some models, the Wi-Fi version of this work around will still
 fail. If this is the case, perform Smart Install. Once Ot is on the
 screen connect wired and run Overall Checkup. Then Upload Results



■ Overall checkup

Preparation

- 1) Check the water supply and drainage connections.
- 2 Please close the door correctly.

Diagnostic list

- 1 Drain test (1st)
- 2 Water supply test
- (3) Cleaning nozzle test
- 4 Drain test (2nd)
- (5) Dry motion test